



GENERAL NOTES

- ① - BUTTERFLY VALVE, SEE PLANS FOR LINE SIZE.
- ② - STRAINER, SEE PLANS FOR LINE SIZE.
- ③ - INSTALL TWO (2) PRESSURE GAUGES WITH ISOLATION BALL VALVE ON SUCTION AND DISCHARGE SIDE OF PUMP.
- ④ - PROVIDE A MINIMUM OF FOUR (4) PIPE DIAMETERS OF STRAIGHT RUN FROM SUCTION FLANGE TO NEXT FITTING EXCLUDING EXPANSION JOINT.
- ⑤ - EXPANSION JOINT, SEE PLANS FOR LINE SIZE.
- ⑥ - CHECK VALVE, SEE PLANS FOR LINE SIZE.
- ⑦ - FACTORY INSTALL DIFFERENTIAL PRESSURE SENSOR WIRED DIRECTLY TO INTEGRAL VFD.
- ⑧ - PUMP IS BASE MOUNTED TO CONCRETE HOUSE KEEPING PAD WITH 4 BOLTS. CONTRACTOR MAY PROVIDE 4 CYLINDRICAL RUBBER VIBRATION ISOLATORS BETWEEN THE PUMP BASE AND HOUSING KEEPING PAD IF CALLED OUT ON PLANS.
- ⑨ - 4" CONCRETE HOUSE KEEPING PAD.
- ⑩ - DEPENDING ON PUMP SIZE IT IS RECOMMENDED TO PROVIDE A CEILING MOUNTED EYELET DIRECTLY ABOVE PUMP FOR FUTURE MAINTENANCE.

1

VERTICAL MULTISTAGE PUMP DETAIL

SCALE: NTS



DRAWING TITLE:
GRUNDFOS CRE-DP PUMP DETAIL FOR
ENGINEERING DOCUMENTS

DRAWING NUMBER:
014

DRAWN BY
BM

LAST REVISED
05/10/2022

DRAWING SCALE
NTS

THE DOCUMENT AND ALL INFORMATION SHOWN IS PROPERTY OF HURLEY ENGINEERING, INC. THIS DOCUMENT IS NOT TO BE REDISTRIBUTED OR COPIED OR USED FOR THE MANUFACTURING OF EQUIPMENT WITHOUT PRIOR WRITTEN CONSENT FROM HURLEY ENGINEERING, INC.

QR CODE

